

TENDER DOCUMENT

FOR

Construction of main gate at Belgoria.

Tender Notice No : 03 / 2010-11

PLACE OF WORK : JRDA Office, Dhanbad

PART – II

Price Bid

**JHARIA REHABILITATION AND DEVELOPMENT AUTHORITY
HATIA GOLF GROUND ROAD, DHANBAD.**

Construction of main gate at Belgoria.

TENDER NOTICE NO : 03 / 2010-11

SYNOPSIS

I/We have gone through the Bills of Quantities in details in the attached sheets and I/We hereby quote my/our rates as follows :-

.....% (..... (in figures) (in words).....)

Percent above/below the estimated rates, amounting to (Rs.....) (in figures) Rs..... (in words)

Signature of the Contractor

(Name of the Contractor)

Construction of Main Entrance Gate, Jharia Vihar Township at Belgoria, Dhanbad

SN	Item	Unit	Qty	Rate	Amount
1	Earth work in excavation in foundation trenches in hard soil (vide classification of soil item - B) and disposal of excavated earth a obtained to a distance up to 50 M including all lifts with leveling ramming the foundation trenches removing roots of trees shrubs all complete as per approved design and per building specification and direction of E/I and extra for earth work in hard soil as per specification and direction of E/I	cum	7.000	48.05	336.35
2	Providing P.C.C./R.C.C. M-75 with normal mix of (1:4:8) in foundation and plinth with approved quality of stone metal grade IV (37 mm to 22.4 mm size) and clean coarse sand of F.M. 2.5 to 3 including screening, shuttering, mixing cement concrete in cement mixer and placing in position, vibrating, striking, curing, tax and royalty all complete job as per building specification and direction of Engineer in charge.	cum	0.500	2267.20	1133.60
3	Providing P.C.C./R.C.C. M-150 with normal mix of (1:2:4) in foundation and plinth with approved quality of stone chips 20 mm to 6 mm size graded and clean coarse sand of F.M. 2.5 to 3 including screening, shuttering, mixing cement concrete in cement mixer and placing in position, vibrating, striking, curing, tax and royalty all complete job as per building specification and direction of Engineer in charge.	cum	2.500	3456.05	8640.13
4	Providing R.C.C. M-150 with nominal mix of (1:2:4) in coloums with approved quality of strone chips 20 mm to 6 mm size graded and clean coarse sand of F.M. 2.5 to 3 including screening, shuttering, mixing cement concrete in mixer and placing in position, vibrating striking, curing (but excluding the cost of reinforcement, taxes and royalty all complete job as per building specification and direction of E/I	cum	2.600	4023.35	10460.71
5	Providing R.C.C. M-150 with nominal mix of (1:2:4) in beam all types with approved quality of stone chips 20 mm to 6 mm size graded and clean coarse sand of F.M. 2.5 to 3 including screening, shuttering, mixing cement cocrete in mixer and placing in position, vibrating, striking, curing (but excluding the cost of reinforcement, taxes and royalty all complete job as per building specification and direction of E/I	cum	2.600	4810.00	12506.00
6	Providing R.C.C. M-150 with nominal mix of (1:2:4) in roof slab with approved quality of stone chips 20 mm to 6 mm size graded and clean coarse sand of F.M. 2.5 to 3 including screening, shuttering, mixing cement concrete in mixer and placing in position, vibrating, striking, curing (but excluding the cost of reinforcement, taxes and royalty all complete job as per building specification and direction of E/I	cum	0.250	4430.40	1107.60

7	Providing 12 mm cement plaster (1:3) with clean coarse sand of F.M. 1.5 including screening, curing with all leads and lifts of water, scaffolding taxes and royalty as per building and direction of E/I	sqm	45.000	76.15	3426.75
8	Providing two coat of snowcem of approved shade and make over a coat of cement of primer on new surface including preparing the plastered surface smooth with sand paper, soaping, curing and taxes all complete as per building specification and direction of E/I	sqm	45.000	40.95	1842.75
9	Providing TMT steel reinforcement above 8 mm to 12 mm dia bars as per approved design and drawing including carriage of M.S. roads (Straight or in coils) to work site, cutting, bending end binding with annealed wire with cost of wire removal of rust placing the rods in position all complete as per building specification and direction of E/I	MT	0.720	42974.00	30941.28
10	Making with raised 25 mm cement plaster (1:4) numbering concrete surface and for working load clarification at end of parapets including cost numbering and painting as per MOST specification and direction of E/I including cost of all labour materials, royalty and taxes etc all complete job.	each	40.000	99.30	3972.00
11	Earth filling in foundation trenches and plinth in layers not exceeding 150 mm thick will watered rammed, fully compacted and fine dressed with earth obtained from excavation of foundation trenches with a lead of 50 mm and lift of 1.5 all complete as per building specification and direction of E/I (Mode of measurement compacted volume)	cum	3.700	16.00	59.20
12	Carriage rate of materials by diesel turck (8 mt. capacity) including loading, unloading and stacking on pucca road but including contractors profit.				
	Cement lead of 10 k.m.	MT	3.000	111.76	335.28
	Sand lead of 35 k.m.	cum	5.000	357.18	1785.90
	Stone metal 40 mm of 8 k.m.	cum	0.500	194.76	97.38
	Stone chips 20 mm of 8 km	cum	8.000	178.78	1430.24
	Steel lead of 10 k.m.	MT	0.720	111.76	80.47
Total :				Rs.	78155.63

TENDER DOCUMENT

FOR

Construction of main gate at Belgoria.

Tender Notice No : 03 / 2010-11

PLACE OF WORK : JRDA Office, DHANBAD

PART – I

TECHNICAL BID

JHARIA REHABILITATION AND DEVELOPMENT AUTHORITY
HATIA GOLF GROUND ROAD, DHANBAD.
JHARKHAND

झरिया पुनर्वास एवं विकास प्राधिकार, धनबाद ।

निविदा आमंत्रण सूचना संख्या 03/2010-11

1. विज्ञापन दाता का नाम – अधीक्षण अभियंता, धनबाद ।
2. निविदा पत्र प्राप्त करने की अवधि एवं समय – 18.11.10 से 20.11.10 तक 4.00 बजे अपराह्न
3. निविदा जमा करने की अंतिम तिथि – 22.11.10 को 3.00 बजे अपराह्न तक
4. निविदा खोलने की तिथि एवं समय – 22.10.10 को 3.30 बजे अपराह्न
5. परिमाण विपत्र बिक्री का स्थान – झरिया पुनर्वास एवं विकास प्राधिकार, धनबाद ।
6. निविदा जमा करने एवं खुलने का स्थान – झरिया पुनर्वास एवं विकास प्राधिकार, धनबाद ।
7. कार्यों का विवरणी :-

क्र0	कार्यों का विवरणी	प्राक्कलित राशि	अग्रधन की राशि	परिमाण विपत्र का मुल्य	कार्य की अवधि
1.	मौजा बेलगड़िया स्थित विस्थापित आवासीय परिसर मुख्य प्रवेश द्वार का निर्माण ।	रु0 78,156.00	रु0 1,564.00	रु0 100.00	दो माह
2.	जे0आर0डी0ए0 कार्यालय, धनबाद में जमीन मरम्मत, रंग रोगन एवं झाड़ी काटने का कार्य	रु0 44,227.00	रु0 885.00	रु0 100.00	एक माह

- 8 भवन निर्माण विभाग, झारखण्ड सरकार में समुचित श्रेणी में निबंधित संवेदक ही निविदा में भाग ले सकते हैं या अन्यत्र समकक्ष कार्य अनुभव रखनेवाले ठेकेदार भी अधीक्षण अभियंता से आदेश लेकर निविदा में भाग ले सकते हैं ।
- 9 निविदादाताओं को व्यक्तिगत रूप से पहचान पत्र के साथ उपस्थित रहने एवं वैध अधिकार पत्र प्रस्तुत करने पर ही निविदा कागजात दिए जायेंगे ।
- 10 परिमाण विपत्र क्रय हेतु पैन नम्बर, वाणिज्य कर सफल प्रमाण पत्र, निबंधन की अभिप्रमाणित सुस्पष्ट छाया प्रति प्रस्तुत करना होगा ।
- 11 निविदादाता दो लिफाफा पद्धति के अनुसार प्राप्त की जायेगी जिसमें एक लिफाफा टेक्नीकल बीड एवं दुसरा लिफाफा प्राइस बीड का होगा। दिनांक 22.11.10 को केवल टेक्नीकल बीड का लिफाफा खुलेगा। टेक्नीकल बीड में जो निविदानुसार क्वालिफाई करेगे उन्ही का प्राइस बीड इसके हेतु निर्धारित तिथि को खोला जायेगा। शेष संवेदको को प्राइस बीड बिना खोले उन्हे लौटा दिया जायगा। टेक्नीकल बीड एवं प्राइस बीड का मुहरबन्द लिफाफा एक तीसरा लिफाफा में सील कर दिनांक 22.11.10 को डालना है।
- 12 दो लिफाफा पद्धति से निविदित कार्यों के निविदाकारों को टेक्नीकली क्वालीफाई करने हेतु निम्नलिखित अहर्ता को पुरा करना अनिवार्य होगा । निम्नांकित अहर्ताओं को धारित नही करने वाले निविदा प्रस्ताव का प्राइस बीड नहीं खोला जायगा ।
 - क) मुख्य सवेदक (प्राइम कान्ट्रैक्टर) के रूप में समान कार्य का अनुभव निविदा आमन्त्रित होने वाले दिन के पूर्व माह के अन्तिम तिथि से पीछले सात वर्ष पूर्व तीन में से एक होना अनिवार्य होगा ।

- i) प्राक्कलित राशि के 80% राशि के समतुल्य या ज्यादा का एक कार्य सफलता पूर्वक पूर्ण करने का अनुभव ।
या
- ii) प्राक्कलित राशि के 50% राशि के समतुल्य या ज्यादा का दो कार्य सफलता पूर्वक पूर्ण करने का अनुभव ।
या
- iii) प्राक्कलित राशि के 40% राशि के समतुल्य या ज्यादा का तीन कार्य सफलता पूर्वक पूर्ण करने का अनुभव ।

एतद संबंधी प्रमाण पत्र संलग्न करना अनिवार्य होगा ।

ख) मुख्य संवेदक (प्राईम कान्ट्रेक्टर) के रूप में निविदा दाता का असैनिक अभियंत्रण कार्यो का पीछले तीन वित्तिय वर्षो में कूल पलटाव (टर्ण ओवर) प्राक्कलित राशि का 90% के समतुल्य राशि या अधिक होना अनिवार्य होगा। एतद संबंधी प्रमाण पत्र संलग्न करना अनिवार्य होगा ।

ग) समान कार्य का मतलब :-

- क्रम संख्या 1 के कार्य के लिए - i) असैनिक अभियंत्रण कार्य ।
क्रम संख्या 2 के कार्य के लिए - ii) भवन मरम्मती संबंधी असैनिक कार्य ।

- 13 संवेदक को निविदा के साथ कार्य का समयवद्ध कार्य योजना समर्पित करना अनिवार्य होगा ।
14. संवेदक को किये गये कार्य का सभी गुणवत्ता नियन्त्रण जाँच रिपोर्ट समर्पित करने के उपरान्त ही विपत्र का भुगतान किया जायेगा ।
15. सरकार द्वारा मजदूरों के लिए स्वीकृत की गई वर्तमान दर का भुगतान करना अनिवार्य होगा ।
16. अधोहस्ताक्षरी तथा सक्षम पदाधिकारी को किसी भी निविदा को बिना कारण बताये रद्द करने एवं एक से अधिक संवेदको में कार्य बाँटने का अधिकार सुरक्षित रहेगा ।
17. परिमाण विपत्र का मुल्य जो लौटाई नही जायेगी, राष्ट्रीय बैंक द्वारा निर्गत बैंक ड्राफ्ट के माध्यम से ली जायेगी, जो अधीक्षण अभियंता, झरिया पुनर्वास एवं विकास प्राधिकार, धनबाद के पदनाम से निर्गत होगा ।
18. अग्रधन की राशि एन0एस0सी0 के आठवॉ निर्गत या 3/5 वर्षीय पोस्ट ऑफिस का सावधि जमा प्रपत्र या बैंक ड्राफ्ट, जो अधीक्षण अभियंता झरिया पुनर्वास एवं विकास प्राधिकार, धनबाद के पक्ष में निर्गत/ प्रतिज्ञापित होगा ।
19. एकरारनामा के अवधि में कार्य पूर्ण नही करने पर नियमानुसार कारवाई की जायेगी। किसी भी प्रकार का अवधी विस्तार स्वीकृत नही किया जायेगा ।
20. सशर्त निविदा मान्य नही होगी ।
21. निविदा जिन सम्वेदक के पक्ष में निर्णित होगा इन्हे एक सप्ताह के अन्दर एफ-2 पर एकरारनामा कर कार्य प्रारम्भ करना होगा, अन्यथा विलम्ब होने पर अग्रधन की राशि जप्त कर ली जायगी ।
22. विशेष सूचना के लिए अधोहस्ताक्षरी के कार्यलय से मिले या सूचना पट्ट पर देखे ।
23. खनीज समनुदान नियमावली 1972 के नियम (10) का अनुपालन करना होगा । सभी व्यवहारिक लधु खनीज को खनन पदाधिकारी द्वारा सत्यापित कार्य की एम0 एन0 एफ0 उपलब्धता पर सम्पादित कार्यो का भुगतान किया जायगा ।
24. परिमाण विपत्र में दर्शाये गये दर से 15% से कम की निविदा दर अमान्य होगी ।

25. निविदादाता जिस कार्य के लिए निविदा दे रहे है वे स्वयं स्थल भ्रमण एवं सर्वे कर ही और उसकी सही स्थित से संतुष्ट होने के बाद ही निविदा दर अंकित करें ।
26. सरकार द्वारा समय-समय पर जारी निर्देशो अनुदेशो का पालन करना अनिवार्य होगा ।
27. संवेदक त्रुटिपूर्ण सामग्रियो की आपूर्ति एवं गलत व्यवहार के लिए पूर्णतः दोषी माने जायेगे ।
28. सिमेन्ट एवं छड़ की खरीदगी संवेदक के विभाग द्वारा अनुमोदित कम्पनी से करनी होगी ताकी गुणवत्ता पर नियंत्रण रखा जा सके ।
29. किसी भी तरह का दर बढ़ोतरी मान्य नही होगी ।
30. कार्य की प्राक्कलित राशि एवं तदनुसार अग्रधन का राशि घट बढ़ सकती है ।
31. इस निविदा को Web site –<http://www.jrda.in> पर देखा जा सकता है ।

अधीक्षण अभियंता
झरिया पुनर्वास एवं विकास प्राधिकार,
धनबाद ।

ज्ञापांक : दिनांक:

प्रतिलिपि :- मुख्य महाप्रबंधक, झरिया पुनर्वास एवं विकास प्राधिकार ।

Web emission, जे0 सी0 मल्लिक रोड, हीरापुर, धनबाद – कृपया संलग्न निविदा दस्तावेज एवं इस N.I.T. को जे0आर0डी0ए0 web site – <http://www.jrda.in> में प्रकाशन करने की कृपा करें।

अधीक्षण अभियंता
झरिया पुनर्वास एवं विकास प्राधिकार,
धनबाद ।

PART - I

**JHARIA REHABILITATION AND DEVELOPMENT AUTHORITY
HATIA, GOLF GROUND ROAD, DHANBAD.
JHARKHAND,INDIA**

TENDER DOCUMENT

NAME OF WORK : Construction of main gate at Belgoria.

PLACE OF WORK :

NAME OF CONTRACTOR :

ADDRESS :

TENDER NOTICE NO : 03/2010-11

DATE & TIME OF RECEIPT OF TENDER : 22.11.10 AT 3.00 P.M.

DATE & TIME OF OPENING OF TENDER : 22.11.10 AT 3.30 P.M

DATE OF ISSUE OF TENDER DOCCUMENT : From 18.11.10 to 20.11.10 between
10.30 AM to 4.00 PM.

MONEY RECEIPT NO & DATE
For issue of Tender Document :

SIGNATURE OF ISSUING AUTHORITY

TENDER DOCUMENT

FOR

**JHARIA REHABILITATION AND DEVELOPMENT AUTHORITY
HATIA, GOLF GROUND ROAD, DHANBAD.
JHARKHAND,INDIA**

DETAIL TO BE FURNISHED BY THE TENDERER

1. Name of the tenderer :
2. Permanent address :
3. Local or Temporary Address :
4. Registration No :
5. Details of Earnest money deposit :
6. Up to date Income Tax clearance Certificate :
8. Up to date sales Tax clearance Certificate :
9. Certified copy of Labour license :

This B.O.Q issued to Sri :
Address :

Signature of Contractor

Name of the contractor

JHARIA REHABILITATION AND DEVELOPMENT AUTHORITY
DHANBAD

Detail Notice For Inviting Tenders

1. Sealed tenders on prescribed bill of quantity to be eventually drawn in P.W.D form No. F2 (Revised) are invited for the works of :-
Construction of Main gate at Belgoria township.
from the contractors registered in the appropriate category in Jharkhand Govt. Other contractors having requisite experience are also eligible to participate in the tender.
2. Detailed estimates, plans and specification for the work can be seen in the office of the JRDA, Dhanbad during working hours on working days except the day of opening the tender.
3. Tender document containing notice for inviting tender, bill of quantities, details to be furnished by the tenderers and general guidance and special condition can be obtained from the office of JRDA, Dhanbad during working hours on any working days from **18-11-10** to **20-11-10** on payment of the amount as indicated which is non refundable.
4. Tender document will be issued only on production of sale tax clearance certificate & PAN NO on request with an application submitted up to **04.00 pm** on **dated 20-11-10**
5. Tender will be received up to **03.00 pm on 22-11-10** and will be opened on the same day at **03.30 pm** in presence of the intending tenderers or their authorised agents. In the event of the specified date for the submission of bids being declared a holiday, the bids will be received upto the appointed time on next working day.
6. Time period of the work is :- **Two months** from the date of written order to commence the work.
7. Tenderers are required to deposit requisite earnest money in shape of National Saving Certificate (8th issue) or Postal Time Deposits 3/5 years, duly pledged to the Superintending Engineer, JRDA, Dhanbad or Bank draft issued by any nationalised bank in favour of Superintending Engineer, JRDA, Dhanbad, failing which the tender will be invalid.
8. When a tender is selected and accepted, the tenderer shall deposit the requisite amount of the initial security money. The amount of earnest money will be converted into a part of the initial security money which will have to be augmented to cover the initial security deposit augmentation (five % of the value of the tender). The same can be in any of the form as detailed in the paragraph 7 above.
9. The total security deposit will be 10% (Ten percent) of the agreement amount. Remaining 5%(Five percent) shall be either recovered from the contractor by deduction from his running account bill at the rate of 5%(five percent) of the total amount of each bill.
10. The earnest money deposited by the selected tenderer which accompanied the tender will be forfeited in case he fails to deposit the balance amount towards 5%(five percent) initial security deposit or to sign the agreement within 10 days of being called upon to do so after acceptance of his tender.
11. The department reserves the right to reject any or all tenders or accept any tender considered advantageous to the department.

12. The tender should be accompanied with up to income tax Pan No. and sales clearance certificate failing which the tender shall be liable to be rejected.
13. The tenderers are also required to submit the certified copy of labour license obtained from the labour department of the area failing which the tender shall be liable to be rejected.
14. This notice for inviting tenders will form an integral part of the documents and consequently this should be submitted along with the tender with every page duly signed as token of acceptance.
15. For details to be furnished by the tenderer, a separate sheet is attached with the BOQ which should consequently be submitted along with the tender after furnishing all details in full duly signed in token of acceptance failing which the tender shall be liable to be rejected.
16. The General guidance and special condition attached (i.e. PART –I) and the BOQ (i.e. PART –II) will form an integral part of the contract documents and pages duly signed in token of acceptance.
17. The tenderers should quote their rates not item wise but only in any one of the three ways in terms of EQUAL OR PERCENTAGE BELOW or PERCENTAGE ABOVE, indicated at the **synopsis** of BOQ both in figures and words, tenderers should strike out those which are not applicable to them, duly signed failing which the tender shall be liable to be rejected. In case of any difference in the rates of figures and words, minimum will be taken into consideration.
18. If any tenderer quotes their rates item wise or attempts a modification in the rates shown in the BOQ their tender will be liable for rejection. Any cutting done by the tenderers must be signed. No overwriting will be allowed.
19. The tenderers should not stipulate any additional condition in their tender for increase of rates due to increase in the rates of Taxation, Rly freight etc. No escalation clause in respect of rise and fall of prices shall be entertained in the tender. Tender with any condition shall be liable for rejection at the discretion of the accepting authority.
20. The tender will be liable for rejection on the ground of unworkable rates quoted by the tenderer.
21. Each page of the tender documents must invariably be signed by the tenderer. Any page without signature shall make the tender invalid.
22. The rates shown in the BOQ are inclusive of all taxes, royalties and shall include other incidental charges and carriage of all materials which have been stipulated to be delivered at departmental godown to work site.
23. The selected tenderer will have to follow strictly the condition laid down in the minimum wages act during the period of construction.
24. It will be obligatory for the tenderers to keep their offers open for acceptance for a period of 120 days from date of opening of price bid or revised price bid if any which ever is later. After that period, a tenderer shall have the option for withdrawing the tender in writing. In that case the earnest money shall be returned/refunded in full.
25. No payment however shall be made until the agreement is executed.
26. The tenderer should get themselves acquainted with the working condition of the site locality and the details of work to be carried on before submitting the tender.

27. In the event of the tender being submitted by a firm, it must be signed by each partner there of or it shall be signed by a person holding a power of attorney authorizing him to do so and which shall be produced on demand.
28. The details of works and their estimated value, the cost of tender paper and amount required for earnest money deposit are as under.

SN	Name of work	Estimated Amount	Cost of Tender paper	Earnest Money
01	Construction of main gate at Belgoria.	Rs. 78,155.63	Rs. 100=00	Rs. 1564=00

29. If required, the negotiation letter shall be issued twice only. The tenderer failing to negotiate even after final notice, his/their tender shall not be further considered and no representation what so ever will be entertained in future.
30. The contractor shall have to procure all the required materials at their own cost for which no compensation or extra charges are payable to the contractor.
31. Procurement of Cement is responsibility of the contractor. The agency may be given cement at the agreement rate for purchase of cement between Distt. Admn. and Cement manufacturer for use in various government works, if available. However the cost of cement have to be borne by the contractor and payment is to made to the cement manufacturer directly.
32. The Earnest Money Deposit is to be submitted in a separate Envelope altogether, superscribing "Earnest Money Deposit"; and not inside the envelope containing Part I or Part II of the Bid.
33. The Part I & Part II should also be put into separate sealed envelopes superscribed as such. Thereafter all the three envelopes should be submitted in a sealed envelope with appropriate superscription.

Superintending Engineer
 Jharia Rehabilitation and Development Authority
 Dhanbad.

**JHARIA REHABILITATION AND DEVELOPMENT, AUTHORITY
HATIA GOLF GROUND ROAD, DHANBAD**

GENERAL GUIDANCE AND SPECIAL CONDITIONS

1. Tender Documents with all its encl., complete in all respect as per N.I.T. should be enclosed in a sealed cover for each work separately and so submitted by dropping in the office tender box or sent by registered post, so that it may reach to the JHARIA REHABILITATION AND DEVELOPMENT, AUTHORITY before the time fixed to receive the tender.
2. Nature of the work for which tender is being submitted and name of the tenderer submitting the tender must be mentioned on sealed cover in block letters.
3. Tender documents may be submitted with a forwarded letter but must invariably be submitted along with required earnest money, up to date income tax and sales tax clearance certificates and labour license and accordance all details must be furnished on the separate sheet attached the B.O.Q. for the same.
4. The tenderer should furnish details of any similar type of work carried out by the tenderer or in hand of the work and full address of the Principal Engineer. to whom reference can be made if required certified copy of any certificate in this regard would be submitted.
5. The tenderer should furnish details of plants and machineries in possession for the execution of the work such as concrete mixture, vibrator etc. and technical staff they posses and will employ to execute the work.
6. All tender documents are complementary to one another and shall be as fully and effect fully binding on the contract.
7. The tenderer shall study the detailed estimates, plans, specification and design drawing carefully before submitting the tender.
8. The tenderer should be acquainted himself well in advance with the working condition of the site and locality and the detail of work to be carried out there. He shall be presumed to have satisfied himself as to the nature extent and practability of all works, all regards land and buildings available for accommodation that may be required for temporary purpose in connection with the work. He must make his own inquiries for temporary purpose in connection with the work. He must make his own inquiries as to work yard, sites, depots and dumps and as to acquisition of such additional site and areas as may be necessary for temporary purposes during construction. He shall be also presumed to have fully acquainted himself with all details of site, location, availability of all transport of materials and soft water, climate / geological condition labour both skilled and unskilled labour and other laws and regulations and in general with all necessary information and date etc. pertaining to and needed for the work and no claim what so ever in these respects will be entertained by the department.
9. The rates shown in the B.O.Q are inclusive of all taxes, royalties, all other incidental charges and carriage of all materials, which have been stipulated to be delivered at departmental godown to work site and no claim in this respect will be entertained by the department.
10. Taxation, railway freight, incidental charges of materials and labour are payable by the contractor and no claim what so ever in this regard will be entertained by the department.

11. No claim shall be entertained on the ground for fluctuation of rates on labour and materials etc. in the market during the period of filling the tender and completion of the work.
12. The construction of work commence from the date of issue of work order unless otherwise mentioned.
13. Work will be executed as per sanctioned plans and estimate, approved design drawing, and as per orders of the competent authorities received from time to time which will be binding on the contractors. No claim for the change or modification in plans and estimate and design drawings by the competent authority or delay in supply of them will be tenable.
14. The circular specification which basically follow the Indian standard specification in force during the period will be followed during the execution of work accept where otherwise provided for in case such items of work, which is not covered by circle specification laid down by the Engineer in-charge shall be followed which will be final and conclusive.
15. Site for the execution of work will be available as soon as work is allotted to the contractor. In case it is not possible the department is to make entire site available on the award of the work. The contractor will have to arrange his working program accordingly and no claim what so ever for not giving site on award of the work, giving the site gradually will be tenable.
16. The site should be cleaned of all rubbish, leveled and dressed as directed by the Engineer in-charge for proper lay out work. If required bushes, wild shrubs of bushes if any shall be removed as directed by the Engineer in-charge before taking up lay out work by the contractor at his own cost. The cost of masonry work, pegs, string labour and the incidental expenditure in the layout works, are to be born by the contractor and no claim what so ever in this respects will be entertained by the department.
17. The arrangement for all necessary stores labour shed, vats, tools, scaffolding, water supply arrangement, electric supply and welding accessories shall be made by the contractor at his own cost and nothing will rest with the department. The Contractor shall also provide all facilities and medical aid to the labourers / employee at his own cost and no claim what so ever in these respect will be entertained by the department.
18. The contractor will have to maintain a site order book at work site in which all necessary instructions etc will be given by the inspecting officer supervising officer or junior engineer, to follow them. The same will be property of the department and will remain at work site under the control of the Junior Engineer in charge of the work.
19. The contractor shall get the sample of Bricks, sands, stone chips etc approved by the Executive Engineer/Superintending Engineer and approved quality of materials shall be kept in the custody of the Executive Engineer/Superintending Engineer in charge for comparison later on when the contractor complete the advance collection of materials to be used in the work and supplied the materials to be used in the work and supplied the materials during the progress of the work as directed by the Executive Engineer/Superintending Engineer in charge of such collections.
20. Bricks to be used in all bricks works shall be confirmed requirement of relevant I.S.I. code.
21. In all R.C.C. work stone chips and sand of specified size and quality confirming to the Indian standard specification on. 456,464 shall be used.
22. Good and approved quality of lime should be used and sample should be get approved before use in the work.

23. Procurement of water in all season with all leads and lift will be entire responsibilities of the contractor at his own cost and no claim what so ever in this respect will be entertained by the department.
24. The Engineer in charge will have full power if required for removal from the premises of the site of all materials, which are in his opinion are not accordance with the specification and in case of defaults.
25. Engineer in charge will have the liberty to sell much inferior materials at the contractor risk or to remove from site at the contractor cost.
26. Any approach road necessary for carrying of building materials to site of work will have to be constructed by the contractor at his own cost and no claim what ever for the same will be entertained by the department.
27. The contractor shall strictly follow the condition laid down the minimum wage act. He shall also compile with the labour laws, which may be current information, which are required from time to time.
28. The contractor shall arrange and provide labour shade to the laboures from temporary accommodation at site. All other facilities like light, water supply, medical aids, labour protection cost and any other incidental cost required under minimum wages act and labour laws to be provided by the contractor to the employed labourers and no claim where so ever in these respect will be entertained by the department.
29. The contractor shall make adequate arrangement for the safety of the labourer and protection and precaution for preserving their health during the execution of the work. He will be responsible for any accident that take place at his work site and adequate compensation for the same will be have to be paid by him as directed by the competent authority. No claim what so ever in this respect will be entertained by the department.
30. The contractor shall employ sufficient number of skilled and experienced labour to the job in order to achieve proportionate progress in time given to the work. During execution of work if his any mistry or labour if found avoiding instruction to follow he shall be turn out at once from the site.
31. Qualified engineer for supervision to the satisfaction of the Engineer in charge will have to the engaged by the contractor as per requirement.
32. In all electrical works the contractor will have to engage licensed electrical wire men/contractor.
33. The contractor shall when he is not personally on the site of the work invariably place and keep on such site a proper qualified agent, duly authorized and to act on behalf of and to receive on his behalf all orders and instruction from the E/IC in relation to such work, including the order required in permitted under the contractor or to be given to the contractor by the E/IC. All such order and instruction given to and all acts done by such agent shall be binding to the contractor as if such orders and instruction where given to him such acts have been done by him.
34. All notices communication reference and complains issued or made by the E/IC or by his representative to the contractor or his authorized agent in connection with the work shall be in writing. And no notice, communication, reference or complaint not in writing shall be valid.
35. The contractor shall take requisite precaution and use his best endeavor to prevent any riotous and unlawful behaviors by or among his workmen and others employees on the work

and he will be responsible for the preservation of the peace and protection of the habitants and security of property in the neighborhood of the work.

36. The contractor is responsible for the soundness from all points, of the materials being used in the work like bricks, stone chips and steel etc. If any test from such materials are conducted by the department for the proof of their soundness (from all point of views) the whole cost involve is to be born by the contractor and will be recovered from his bill and no claim what so ever in this respect will be entertained by the department. The test report received from the test house will be biding upon the contractor if test report is unsatisfactory the materials will be rejected.
37. The contractor is also responsible for the soundness (from all point of view) of the RCC work being done in the building work if any test in cube test of RCC work done of being done are conducted by the department through quality control wing of the department for the soundness form all point of view the whole cost involve is to be born by the contractor and recovered from his bill. If the test reports is found unsatisfactory such RCC work done will be rejected and cost of dismantling and reconstruction of the same will be born by the contractor and no claim what so ever in this respect will be entertained by the department.
38. The contractor is also responsible for the satisfactory tests and result of all RCC work done mortar used and all other work done in the building work. For that he should provide and make arrangement for all required number of samples for test and analysis. Only on satisfactory test and result RCC work and all other works done will be accepted. If the test report found unsatisfactory, such work done will be rejected and cost of dismantling and reconstructing, the same will be born by the contractor and no claim what so ever in these respect will be entertain by the department.
39. No claim be entertained for cleaning and scrapping rust and other element from steel.
40. For RCC works all concreting and shuttering materials arranged and procure by the contractor at his own cost shall be a good quality and requisite thickness and diameter. All the concreting and shuttering work done in RCC work must be rigid and should so that it may not deform or disturb during steel work and casting with vibration arrangement by the contractor at his own cost. In case of shuttering for RCC column and stiffeners steel plates of requisite thickness shall be used and not the wooden planks to give smooth surface.
41. All RCC works as well as PCC works shall be machine mix properly with concrete mixture machine arranged by the contractor at his own cost and submerged with 2" constant head of water over horizontal concrete.
42. If the mixing of mortar and concrete and compaction of concrete not done with machine mixture and vibrator, then 10% extra cement by volume added in the mix on the cost of contractor for which no claim what so ever in these respect will be entertained by the department.
43. Where joints in reinforcement in all RCC works can not be avoided due to required length of steel bars whether mild or tor steel they will be form by over lapping to a length 45 times of diameter and tied with anodized soft iron wire.
44. During casting of RCC or PCC in foundation the trenches shall be pumped out for which no extra payment to contractor shall be made by the department.
45. Lime concrete intending for terrace over RCC roof slab also be machine mixed as per RCC work.

46. Over all in structural work except plastering clean course sand shall be used. For plastering clean medium sand shall be used and should be screened 256 mesh in one Sq. inch. Placed 45-degree incline before used in the work.
47. The jams and soffits of doors and windows openings should be smooth true to plumb and suitable space will have to be left for receiving W-1 clamps as per direction of engineer in charge for which no claim shall be entertained by the department.
48. Suitable recess for fixing clamps doors and windows join works, railing required shall have to be provided by the contractors. In brick walls, RCC column and RCC roof recess shall be provided as per direction of the E/IC without any cost.
49. The teakwood and sal wood be well-seasoned and free from sap wood cracks knots and other timber defects. The manufacturing chauhats and frame of shutters of any structure should be got approved before use in the work.
50. All fittings and fixtures for doors and windows shall be got approved by the E/IC. will in advance before use in the work. The approved fittings and fixture shall be mounted on a wooden board and always kept at site of work open for inspection and one such mounted board will be deposited in the office of the S.E. / Ex.Engg. (C) at the cost of the contractor.
51. Flat iron for making grill for windows, handrail for staircase etc. shall be procured by the contractor himself.
52. All points of welding grills etc. must be electrically welded from all sides of the joints to give clean smooth and strong joints. The sample of grills be get approved by S.E. / Ex. Engg. (C) before taking of mass manufacture.
53. Where not other wise specified 4 mm thick glass panes weighing 10 kg per sqm. only shall be used in all glazed shutters.
54. After completion of work building floor should be thoroughly washed and clean, the ugly mark on glass panes shutter etc. shall be removed and damages made good. The under work of paints cement etc. shall be removed and cleaned nicely, by the contractor at this own cost.
55. The contractor shall remove all the surplus materials rubbish etc. and leave the site clean and tidy after leveling and dressing the premises of the work as desire by the E/IC. and then the work shall be considered as complete.
56. The contractor will have to make and maintain diversion at his own cost if required. He will also have to provide barrier, light danger signal and night chaukidar etc. at his own cost to prevent any accident.
57. The department will not be held responsible for the work stopped at the stage of progress to reason beyond the control of the dept. And no claim what so ever in this respect will be entertained by the department.
58. From the commencement of the work to the completion of the work, They are to be under the contractor charge. The contractor is to be held responsible for and to make good all injuries, damages and repairs occasioned or rendered necessary to the same by the fire or other cause and they are to hold the Governor of Jharkhand harmless from any claim for injury to persons and structural damage to property happening from any neglect default, want to prop case on misconduct in the part of the contractor or any one his employee during the execution of work. In case of accidents, the contractor(s) shall be responsible for compliance with all the requirements imposed by workmen's compensation Act. or any other similar laws in force, and the contractor(s) shall indemnify the J.R.D.A. against any claim on this account.

59. No claim shall be entertained for loss due to earth quake, flood, cyclone, epidemic, war riot or any other natural calamities or emergency, act of enemies and damages so caused will have to be made good by the contractor at his own cost.
60. All claims for work done beyond the agreement must be submitted by 10th of each month failing which they will be treated as time barred.
61. During execution of work any item which is provided in the bill of quantity is not required to be done due to change of specification, contractor will have no claim whatsoever that item is not got done through him.
62. The contractor shall offer all facilities to the departmental officers for inspection, supervision taking and checking bills etc and any damages in the process will be made good by the contractor at his own cost.
63. In case of T.L. inverted and rectangular beam only the projecting below or above the slab shall be measured for payment.
64. For the purpose of payment of brick work B.W. will be done with new size of brick as per latest I.S.I. specification by the department.
65. No claim for extra thickness of more than ½” thick cement plaster in either side of 10” or 5” thick wall be entertained by the department.
66. All wooden salvaged materials will have to be returned to the department unless at the rate of 10% value of the replaced new wood will be deducted from the bill of the contractor.
67. Amount of royalty will be realized at the rates fixed by the mining department.
68. Amount of Income Tax will be realized at the rates fixed by the Income Tax department.
69. Dues will be realized under public recovery act.
70. It is understood and agreed that no extra payment shall be admissible to the contractor consequent on any alleged or miscalculation arising out of any other mistake or factor not specifically provided for in the contract.
71. In case of any undue hindrances occurred, an application by the contractor within 10 days of the date such hindrances occurred to the responsible to the competent authority for completion of work.
72. The department will not be responsible for lapse time for non-availability or delay supply of departmental materials for which no claim demurrages whatsoever in these respects will be entertained by the department.
73. The contractor shall have to produce clearance certificate in respect of payment of royalty etc. for the minerals consumed in the work from the concerned District Mining Officer/Asst. District Mining Officer, without which final bill shall not be paid.
74. As per order given H’ble High Court-Ranchi bench dated 8-02-2000 it is brought to the notice of the tenderer that acceptance/rejection of tender shall be in accordance with the circular of department/Vigilance department issued time to time. Ref Letter No.- 2882 (vigilance) dated 13-09-1991 and others.

75. SECURITY DEPOSIT

- i. Tenderers are required to deposit invited earnest money in shape of any of the National Saving Certificate (8th issue) or Postal Time Deposits 3/5 years, duly pledged to the Superintending Engineer, JRDA, Dhanbad or Bank draft / Bank guarantee issued by any nationalised bank in favour of Superintending Engineer, JRDA, Dhanbad failing which the tender will be invalid. Earnest money will not carry any interest.

- ii. When a tender is selected and accepted the tenderer shall deposit the requisite amount of the initial security money. The amount of earnest money will be transferred towards a part of initial security money, which will have to be augmented to cover the initial security deposit. (5% of the value of the tender) . The same can be in any of the form as detailed in the paragraph (a) above.
 - iii. The total security deposit will be 10% (Ten percent) of the agreement amount remaining 5% (Five percent) shall be recovered from the contractor by deduction from his running account bill at the rate of 5% (Five percent) of the total amount of each bill. The security deposit amount will not carry any interest. The bank guarantee towards security deposit shall be valid for a minimum period of one year or six months beyond the period of contract which ever is more.
 - iv. On completion of entire work the E/ic will accept it only after joint inspection with the contractor. After acceptance of the work half of the security deposited money will be released on expiry of a period of six months from the date of issue of completion certificate. Remaining half of the security deposit will be released after period of one year from the date of issue of completion certificate.
76. Sale tax registration and clearance certificate for the last financial year or the last assessment year which ever is later or proof of filling the returns for the previous financial year should accompany the tender.
77. The validity period of the tenders shall be 120 days from the date of opening of price bid or revised bid, if any which ever is later.
78. Any difference detected in the tender/tenders submitted resulting from:
- i. The employees entrusted with the work date and initial all papers, the calculation of which they have checked and that all working sheets are preserved.
 - ii. If on checks there are different between the rate given by the contractor in words and figures or in amount worked out by him, the following procedure shall be followed:-
 - a. When there is a different between the rates in figures and in words, the rates which corresponds to the amount worked out by the contractor shall be taken as correct.
 - b. When the amount of an item is not worked out by the contractor or it does not corresponds with the rates written either in figures or words, then the rates quoted by the contractor in words shall be taken as correct.
 - c. When the rate quoted by the contractor in figures and in words tallies but the amount is not worked out correctly, the rate quoted by the contractor shall be taken as correct and not the amount.
 - d. In the case of percentage rate tender, the contractors are required to quote their rates both in amount as well as in the percentage below/above the rates entered in the schedule. In such cases in the event of Arithmetical error committed in amount by the contractor, the tender percentage and not the amount should be taken into account.
79. The work will carried out as per PWD norms and specification.
80. No interest shall be payable on earnest money. No interest shall be payable on the amounts with held, under the terms of the agreement/work order.
81. Defects liability period :-

In addition to the defect/s to be rectified by the contractor as per terms of the contract/work order, the contractor shall be responsible to make good and remedy at his own expense, defect/s mentioned here under within such period as may be stipulated by the E/ic in writing.

(a) The defect liability period is 1 (one) year after the issue of completion certificate of the work issued by the E/ic

82. the tenderers should quote their rates not item wise but only in any one of the three ways in terms of EQUAL or PERCENTAGE BELOW or PERCENTAGE ABOVE indicated at the foot of B.O.Q. both in figures and words. Tenderers should strike out those which are not applicable to them, duly signed failing which the tender shall be liable to be rejected.
83. On completion of the work all rubbish, debris, brick bats etc. shall be removed from the site by the contractor/contractors at his/their own expense and the site cleaned and handed over to the department and shall intimate officially of having completed the work as per contract.
84. Each pages of the tender document must invariably be signed by the tenderer. Any page without signature shall make the tender invalid.
85. The time allowed for carrying out the work as entered in the tender shall be strictly observed by the contractor and shall be reckoned from the date on which the written order to commence work is given to the contractor. The work shall throughout the stipulated period of the contract be carried on with all due diligence (time being deemed to be the essence of the contract on the part of the contractor) and the contractor shall pay compensation an amount equal to ½ percent on the amount of the estimated cost of the whole work as shown by the tender for every day that the work remains uncommenced or unfinished after the proper date. And further to ensure good progress during the execution of the work the contractor shall be bound in all cases in which the time allowed for any work exceeds one month to complete one fourth of the whole of the work before one-fourth of the whole time allowed under the contract has elapsed one half of the work before one half of such time elapsed and three fourths of the work, before three fourths of such time has elapsed in the event of the contractor failing to employ with this condition, he shall be liable to pay as compensation an amount equal to ½ percent on the said estimated cost of the whole work for every day that the due quantity of work remains incomplete provided always that the entire amount of compensation to be paid under the provisions the clause shall not exceed 10 percent of the estimated cost of the work as shown in the tender.